

WELL PLUGGING RECORD CONSERVATION DIVISION
Wichita, Kansas

Give All Information Completely
Make Required Affidavit

COUNTY Kingman SEC. 17 TWP. 30 RGE. 6w E/W
Location as in quarters or footage from lines:
SW SE SE

Lease Owner Bowers Drilling Co.
Lease Name Riggs Well No. 1
Office Address Box 241 Medicine Lodge Ks.
Character of Well (Completed as Oil, Gas or Dry Hole): Gas
Date Well Completed 1/77
Application for plugging filed 3/30/81
Plugging commenced 4/14/81
Plugging completed 4/17/81
Reason for abandonment of well or producing formation Dry

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie
Producing formation Miss Depth to top _____ bottom _____ T.D. 4472

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
	<u>Surface</u>	<u>0</u>	<u>285</u>	<u>8 5/8</u>		
		<u>0</u>	<u>4138</u>	<u>4 1/2</u>		<u>3640</u>

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Filled hole with sand to 4070 and dumped 4 sx. cement
Pum ped top with Allied cementers, 15 sx. jell 8 sx. hulls
10 sx. jell and 125 sx. 50-50 poz. 4% jell, 3% C.C.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Nicholas Casing Pulling
Box 373 Geneseo Kansas 67444

STATE OF _____ COUNTY OF _____, ss.

(employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) George A. Nicholas
(Address) _____

SUBSCRIBED AND SWORN TO before me this 20th day of April, 1981

My Commission expires: 

Steven K Prickett
Notary Public.

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

RECEIVED
STATE CORPORATION COMMISSION
APR 21 1980
CONSEWAY, WICHITA, KANSAS

Riggs A-1
SW-SE-SE Sec 17-30S-6W
Kingman County Kansas

Commenced: 7-2-79

Completed: 7-14-79

OPERATOR: Bowers Drilling Co.

Depth	Formation	Remarks
From	to	
0	850	Redbed
850	1105	Shale-Shells
1105	1550	Shale
1550	1745	Shale-Lime
1745	2457	Shale
2457	2602	Shale-Lime
2602	3760	Lime-Shale
3760	4070	Lime
4070	4442	Shale
	4442 - TD	

Ran 7 jts of 20# 8 5/8" csg
set @ 285' Cemented w/
225 sks Common 2% Gel
3% CC PD @ 1:00 a.m. 7-3-79

Ran 104 jts of 10 1/2# 4 1/2"
csg set @ 4134' Cemented
w/100 sks 50/50 Posmix
Salt Sat
PD @ 1:00 a.m. 7-14-79

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above
Drillers' Well Log is true and correct to the best of my knowledge and belief and
according to the records of this office.

GABBERT-JONES, INC.

James S. Sutton II
JAMES S. SUTTON II

Subscribed and sworn to before me this 18th day of July, 1979.

Elizabeth J. Edwards
ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission expires February 6, 1983.

