

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Kingman County, Sec. 4 Twp. 29S Rge. 8 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
100' E of C NE

Lease Owner Keener Oil Company
Lease Name Laverna Mayer Well No. 1
Office Address 406 Nat'l Bank of Tulsa - Tulsa, Oklahoma
Character of Well (Completed as Oil, Gas or Dry Hole) dry hole


Date Well completed September 2, 19 77
Application for plugging filed September 2, 19 77
Application for plugging approved September 2, 19 77
Plugging commenced September 2, 19 77
Plugging completed September 3, 19 77

Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Bill Owens - Pratt, Kansas
Producing formation Depth to top Bottom Total Depth of Well 4190'
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface					
	Casing	0	218'	8 5/8"	218'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug at 218' with 35 sacks cement,
plug at 40' with 12 sacks cement,
5 sacks in rat hole. Job completed
at 1:10 A.M., September 3, 1977 by
Halliburton.

RECEIVED
STATE CORPORATION COMMISSION

SEP 07 1977

CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Search Drilling Company

STATE OF Kansas COUNTY OF Sedgwick, ss.
R. M. Stagl (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. M. Stagl
Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 6th day of September, 1977

Maxine Dressen
Maxine Dressen Notary Public.

My commission expires February 22, 1981



DRILLERS LOG

LAVERNA MAYER #1

<u>CASING RECORD:</u> 8 5/8" set at 218' with 200 sacks cement	<u>OPERATOR:</u> Keener Oil Company	<u>DESCRIPTION:</u> 100' E of C NE/4, Section 4-29S-8W, Kingman County, Kansas
<u>TOTAL DEPTH:</u> 4190'	<u>CONTRACTOR:</u> Search Drilling Company	
	<u>COMMENCED:</u> August 26, 1977	
	<u>COMPLETED:</u> September 3, 1977	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand and Clay	0	80	
Sand	80	115	
Red Bed and Shale	115	225	
Red Bed and Shale	225	1035	
Shale	1035	1552	
Lime and Shale	1522	1959	
Lime and Shale	1959	2740	
Lime and Shale	2740	3183	
Lime and Shale	3183	3809	
Lime and Shale	3809	4153	
Mississippi	4153	4174	
Mississippi Chert	4174	4190	
Rotary Total Depth	4190		Dry and Abandoned

RECEIVED
STATE CORPORATION COMMISSION
SEP 07 1977
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SEARCH DRILLING COMPANY

R. M. Stagl
R. M. Stagl

Subscribed and sworn to before me this

My appointment expires:
February 22, 1981

Maxine Dressen
Maxine Dressen Notary Public

