


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

NORTH



Locate well correctly on above
Section Plat

Kingman County, Sec. 36 Twp. 29 Rge. 7 (E) W (W)
Location as "NE/CNW/SW" or footage from lines SW SE NE
Lease Owner Pickrell Drlg. Co.; Wichita, Ks. 67202
Lease Name Coykendall Well No. # 3
Office Address 705 Fourth National Bank Bldg. Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Gas
Date well completed February 26 1963
Application for plugging filed January 5 1971
Application for plugging approved January 5 1971
Plugging commenced January 7 1971
Plugging completed January 11 1971
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production December 21 1970
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Russell Biberstein
Producing formation Mississippian Depth to top 4076 Bottom 4096 Total Depth of Well 4160 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	237	None
				4 1/2	4160	3320

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.


January 7, 1971 Plugged off bottom. Dumped sand to 4050'. Mixed and dumped 4 sx of cement to 4000'.
January 11, 1971 Plugged off top. Set 10' rock bridge from 220' to 230'. Filled 8 5/8" surface casing from 220' to base of cellar with 4 yds. of 3000 lb. P.S.I. ready mix concrete.

RECEIVED
STATE CORPORATION COMMISSION
FEB 16 1971
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor RUSS CASING PULLING, INC.
Address P. O. Box 1082 Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Dale M. Robinson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dale M. Robinson
705 Fourth National Bank Bldg., Wichita, Kansas (Address)
Subscribed and sworn to before me this 15th day of February, 1971
January 19, 1973
Esther Lamone Notary Public



ROTARY DRILLING LOG

COMPANY: PICKRELL DRILLING COMPANY
705 4th Natl. Bk Bldg
Wichita, Kansas

Rotary Drilling Commenced 2-16-63

Rotary Drilling Completed 2-26-63

LOCATION: Coykendall #3, C SW SE NE 36-29S-7W
Kingman County, Kansas

CONTRACTOR: PICKRELL DRILLING COMPANY
Wichita, Kansas

CASING RECORD: 237' (6 jts) 8 5/8" Surface Casing with 180 sacks cement.
Circulated. (131 jts) 4 1/2" Casing - set at 4159' with
100 sacks cement. Completed at 1:30 P.M. February 26,
1963.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

79	Sand	<u>C. F. S.</u>
235	Red Rock	4087
240	Shale	4097
1030	Red rock, shale & shells	4107
1320	Shells and Lime	4114
1550	Shale and Lime	4130
1710	Lime	4140
2935	Lime and Shale	4160
3040	Shale and Sand	
3147	Lime and Shale	
3325	Shale, sand and Lime	<u>Slope Tests</u>
3420	Lime and Shale	1400
3841	Lime	2400
4107	Lime and Shale	3400
4160	Mississippian (RTD)	4000

S. L. M.
2401
3287
3994

RECEIVED
STATE CORPORATION COMMISSION
JAN 6 1971
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, _____, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
By [Signature]
Attorney-in-Fact
C. W. SEBES

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 11th day of March, 1963, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared _____, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

[Signature]
Notary Public
Maxine Blackman

My commission expires: June 21, 1966