


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Kingman County, Sec. 36 Twp. 29 Rge. 7 (E) (W)
Location as "NE/CNW/SW" or footage from lines SE/SE/SW
Lease Owner Fickrell Drilling Company
Lease Name Gaykendall Well No. #1
Office Address North Main, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed Yes 19____
Application for plugging approved Yes 19____
Plugging commenced _____ 4-13 19 57
Plugging completed _____ 4-18 19 57
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. M.A. Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4200' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				<u>4 1/2"</u>		<u>3637'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Measured into TD 4200'.
Plugging started 4-13-57. Finished 4-18-57.
Plugged off bottom with sand back to 4100' and dumped 4 sacks cement with bailer. Shot 4 1/2" casing at 3637'. Pulled pipe out of hole and plugged well with heavy mud to 200' and set permanent rock bridge. Dumped 25 sacks cement. Filled hole with heavy mud to 35' and mixed 10 sacks for cap on well.


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor J.O. Forbes d/b/a Forbes Casing Pulling Co.
Address Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J.O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J.O. Forbes
Box 221, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 19th day of April, 1957.

Betty S. Edman
Notary Public.



PLUGGING
FILE SEC. 36 T. 29 R. 7w
BOOK PAGE 5 LINE 27

RECEIVED
STATE CORPORATION COMMISSION
APR 20 1957
CONSERVATION DIVISION
Wichita, Kansas

ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company
Wichita, Kansas

Rotary Drilling Commenced: 2/24/57

Rotary Drilling Completed: 3/11/57

LOCATION: SE SE SW Sec. 36-29S-7W, Kingman County, Kansas

Coykendall #1

CONTRACTOR: PICKRELL DRILLING COMPANY
Wichita, Kansas

CASING RECORD: 160' (4 jts.) 8 5/8" 22.7# Armco Spiralweld Casing set at 160' with 140 sacks 300# C.C. Cement circulated.

Ran 132 jts. 4197' of 4 1/2" Casing set at 4200' cemented with 110 Sacks 2% gel Cement.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

Sand, Streaks & Clay	55	Circ. for samples at	3735
Red Rock	310		4110
Shale	670		4118
Salt, Shale & Shells	1160		4128
Lime	1800		4140
Shale & Shells	1985		4150
Shale & Lime	2315		4170
Shale	2390		4200
Lime & Shale	2725		
Lime & Sand	2981		
Lime	3074		
Lime & Shale	3290		
Lime	3580		
Lime & Shale	3625		
Lime	4020		
Lime & Shale	4099		
Mississippi	4200 T.D.		

S.L.M. at 1500 - O.K.
3000 - "
4000 - "

Slope Test at 1500 - 0° off
3000 - 0° off
4000 - 0° off

PLUGGING
FILE SEC 36 T. 29 R. 7W
BOOK PAGE 5 LINE 27

The undersigned, C.W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By [Signature] Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

RECEIVED
REGISTRATION COMMISSION
APR 24 1957

On this 23rd day of March, 1957, before me the undersigned, a Notary Public, in and for

the County and State aforesaid, personally appeared C.W. Sebitts to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: July 30, 1958

[Signature]
Notary Public