

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Kingman SEC. 36 TWP. 29S RGE. 7W E/W
Location as in quarters or footage from lines:
C W/4 NW NW

Lease Owner Tenneco Exploration & Production
 Lease Name Krehbiel Well No. 2
 Office Address Ciudad Bldg. Suite 139 3000 United Founders Blvd. Okla. City
 Character of Well (Completed as Oil, Gas or Dry Hole): _____
 Date Well Completed 12-21-60
 Application for plugging filed 8-12-82
 Plugging commenced 9-30-82
 Plugging completed 10-2-82
 Reason for abandonment of well or producing formation Non Productive

Locate Well correctly on above Section Platt.

Was permission obtained from the Conservation Division or it's Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie
 Producing formation Mississippi Depth to top 4094 bottom 4125 T.D. 4185
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	277	none
				5 1/2	4148	2600

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set. MIRU set btm plug w/50 sx 20-40 frac sd capped with 5 sx common cmt. SD WOC. RIH tag top of btm plug @ 2625. Shot 5 1/2 @ 2600. POH LD 25 jts csg. Continue POH 57 jts csg (82 jts total) CO collar to 3' below GL. RDMO. MIRU Howco. Set top plug w/125 sx common cmt, 25 sx gel, 6 sx cotton seed hulls. Weld plate, clean location. RDMO. Plugging complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sargents Casing Pulling Service Box 506 Liberal, Kansas 67901

STATE OF OKLAHOMA COUNTY OF OKLAHOMA, ss.

THOMAS E. PAGE, JR. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Thomas E. Page, Jr.
TENNECO OIL COMPANY
3000 UNITED FOUNDERS BLVD
OKLAHOMA CITY OK 73112

SUBSCRIBED AND SWORN TO before me this 28th day of December, 1982

My Commission expires: August 25, 1984

Nancy S. Moore
 NANCY S. MOORE Notary Public.
 STATE CORPORATION COMMISSION

DEC 30 1982

CONSERVATION DIVISION
Wichita, Kansas

ROTARY DRILLING LOG

OPERATOR: Wilcox Oil Company
 KREMBIEL NO. 2
 W/2 NW NW Sec. 35-29S-7W,
 Kingman County, Kansas

CONTRACTOR: Prime Drilling Company
 COM: 12-9-60
 COMP: 12-21-60

Remarks: Set 5-5/8" surface casing
 at 277' cemented with 200
 sacks cement.

Formations:

Red Bed & Sand Streaks	273'
Red Bed & Shale	1000'
Shale & Lime	1240'
Lime	1635'
Lime & Shale	3016'
Lime	4070'
Lime & Shale	4091'
Lime	4185'
Rotary Total Depth	4185'

Set 5-1/2" casing at 4184' cemented with
 150 sacks common cement, 2% C.C.

We certify the above log is true and
 correct to the best of our knowledge
 and belief.

PRIME DRILLING COMPANY

R.R. McNicol

R. R. McNicol

RECEIVED
 STATE COORDINATION COMMISSION

DEC 30 1962

CONSERVATION DIVISION
 Wichita, Kansas

ROTARY DRILLING LOG

OPERATOR: Wilcox Oil Company
KREHBIEL NO. 2
W/2 NW NW Sec. 36-29S-7W,
Kingman County, Kansas

CONTRACTOR: Prime Drilling Company
CONM: 12-9-60
COMP: 12-21-60

Remarks: Set 8-5/8" surface casing
at 277' cemented with 200
sacks cement.

Formations:

Red Bed & Sand Streaks	278'
Red Bed & Shale	1000'
Shale & Lime	1240'
Lime	1635'
Lime & Shale	3016'
Lime	4070'
Lime & Shale	4091'
Lime	4185'
Rotary Total Depth	4185'

Set 5-1/2" casing at 4184' cemented with
150 sacks common cement, 2% C.C.

We certify the above log is true and
correct to the best of our knowledge
and belief.

RECEIVED
STATE CORPORATION COMMISSION

JUL 28 1962
CONSERVATION DIVISION
Wichita, Kansas

PRIME DRILLING COMPANY

R. R. McNicol

R. R. McNicol