

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-095-20709 - 0000

LEASE NAME Molitor

WELL NUMBER 1

1980 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 2 TWP. 29 RGE. 8 (E) or (W)

COUNTY Kingman

Date Well Completed 4/21/78

Plugging Commenced 8/29/88

Plugging Completed 11/14/88

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR GEAR PETROLEUM CO., INC.

ADDRESS 1075 KSB Bldg. Wichita, KS 67202  
125 N. Market

PHONE# (316) 265-3351 OPERATORS LICENSE NO. 5151

Character of Well Uneconomic

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11/14/88 (date)

by Steve VanGieson (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Filed with application to plug

Producing Formation Mississippi Depth to Top 4135 Bottom N.P. T.D. 4144

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Mississippi	Gas	4139	44	8 5/8	212	None
				4 1/2	4139	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. 11/4/88 Spot 35 SX cement at 1300, pull pipe to 800' and spot 35 SX cement, pull pipe to 300 and circulate 120 SX to surface, pull rest of pipe. Bottom of hole plugged off 8/29/88 with sand from 4120 to 4144 and cement 4070-4120.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor GEAR PETROLEUM CO., INC. License No. 5151

Address 1075 KSB Bldg. 125 N. Market Wichita, KS 67202

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Jim Thatcher

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jim Thatcher

(Address) 1075 KSB Bldg. 125 N. Market


Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 5 day of December, 1988

STATE CORPORATION COMMISSION

Pauletta K. Engels  
Notary Public

My Commission Expires: 8/1/89 DEC 5 1988



CONSERVATION DIVISION  
Wichita, Kansas

Form CP-4  
Revised 07-87

DRILLERS LOG

No. 1 Molitor "A"

CASING RECORD:

8 5/8" @ 212.08'  
w/200 sx cement

4 1/2" @ 4,139'  
w/150 sx cement

TOTAL DEPTH: 4,145'

COMPANY:

Gear Petroleum Company

CONTRACTOR:

Red Tiger Drilling Company

COMMENCED:

April 12, 1978

COMPLETED:

April 21, 1978

DESCRIPTION:

C NW/4 SW/4  
Sec. 2-T29S-R8W  
Kingman County, Kansas

ELEVATION: 1,673' KB

FORMATION

FROM

TO

REMARKS

Surface Soil & Clay

0

80

Red Bed

80

280

Gray Shale

280

1030

Shale

1030

1251

Lime

1251

1655

Shale & Lime

1655

1890

Lime

1890

3370

Lime & Shale

3370

3425

Lime

3425

3855

Lime & Shale

3855

3957

Lime w/Shale Streaks

3957

4043

Lime & Shale

4043

4137

Lime

4137

4145

RTD

4145

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

*Gloria Fawcett*  
Gloria Fawcett

RECEIVED  
STATE CORPORATION COMMISSION

SEP - 1 1988

Subscribed and sworn to before me this 24th day of April, 1978.

CONSERVATION DIVISION  
Wichita, Kansas

*Joyce A. Hagemann*  
Notary Public