


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Kingman County, Sec. 12 Twp. 29S Rge. 9W (E) (W)X
Location as "NE/CNW/SW" or footage from lines NW NE
Lease Owner Rex & Morris Drilling Co.
Lease Name Rohlman Well No. 1
Office Address 625 S. Main, El Dorado, Kans
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed April 2 1971
Application for plugging filed April 2 1971
Application for plugging approved April 2 1971
Plugging commenced April 2 1971
Plugging completed April 2 1971
Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving
Producing formation Depth to top Bottom Total Depth of Well 4530 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	286'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged hole w/1/2 sx hulls and
plug @ 260' and 35 sx cement -
mud to 40' - 1/2 sx hulls and plug
@ 40' - 10 sx cement to bottom of
cellar - plugged rathole w/2 sx
cement. Hole plugged @ 10:30 a.m.

RECEIVED
STATE CORPORATION COMMISSION
APR 7 1971
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Red Tiger Drilling Co.
Address 1720 Wichita Plaza, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

Jim Farrice (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)


1720 Wichita Plaza, Wichita, Kansas

(Address)

Subscribed and sworn to before me this 5th day of April, 1971

Notary Public.

My commission expires July 23, 1974



DRILLERS LOG

No. 1 Rohlman

CASING RECORD:8 5/8" @ 286'
w/250 sx cementCOMPANY:

Rex & Morris Drilling Co.

DESCRIPTION:NW NE
12-29S-9W
Kingman County,
KansasCONTRACTOR:

Red Tiger Drilling Co.

COMMENCED:

March 19, 1971

COMPLETED:

April 2, 1971

TOTAL DEPTH: 4530'

ELEVATION:

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay, Sand & Shale	0	255	
Shale	255	290	
Shale & Shells	290	945	
Shale & Lime	945	3055	
Lime	3055	3157	
Shale & Lime	3157	3460	
Lime	3460	4255	
Chert & Lime	4255	4300	
Chert, Lime & Shale	4300	4337	
Lime	4337	4390	
Chert, Lime & Shale	4390	4435	
Lime & Shale	4435	4484	
Lime	4484	4519	
Lime & Chert	4519	4530	

RECEIVED
STATE CORPORATION COMMISSION
APR 7 1971
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Jim Farrice
Jim Farrice

Subscribed and sworn to before me this 5th day of April, 1971.

Vernon Albert
Notary Public

My Commission Expires:

July 23, 1974