


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Kingman County, Sec. 12 Twp. 29S Rge. (E) 9 (W)
Location as "NE/CNW/WSW" or footage from lines NW NW NW
Lease Owner Charles Ritchie & Strata Drilling, Inc.
Lease Name Tiesmeyer Well No. 1
Office Address Box 355, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 16 1958
Application for plugging filed July 16 1958
Application for plugging approved July 16 1958
Plugging commenced July 16 1958
Plugging completed July 16 1958
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred W. Hampel, Pretty Prairie
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4528 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
					8-5/8"	
					212'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged hole as follows: Plugged at 200' with 35 sacks of cement through drill pipe, plug at 35' with one-half sack of hulls and 10 sacks of cement. Job completed at 10:00 P. M. on July 16, 1958.

RECEIVED
STATE CORPORATION COMMISSION

JUL 24 1958

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Strata Drilling, Inc.
Address Box 355, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Jim B. McWilliams (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jim B. McWilliams
Jim B. McWilliams
Box 355, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 21th day of July, 1958

My commission expires December 14, 1961
Elaine H. Taylor Notary Public.

PLUGGING
FILE SEC 12T 29 R 9W
BOOK PAGE 117 LINE 2

DRILLERS LOG

#1 Tiesmeyer

CASING RECORD: 212' of used 8-5/8" surface casing.
 COMPANY: Charles Ritchie & Strata Drilling, Inc.
 DESCRIPTION: NW NW NW Section 12-29S-9W
 CONTRACTOR: Strata Drilling, Inc. Kingman Co., Kansas
 TOTAL DEPTH: 4528'
 COMMENCED: July 3, 1958
 COMPLETED: July 16, 1958
 ELEVATION: 1705' KB
 1700' GL

D. & A.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand	0	80	Ran 212' (11 Jts.) of used 8-5/8" surface casing; cemented with 175 sacks of Cement, 300 lbs. of Calcium Chloride. DST #1 Packer set @ 4518'. Total Depth 4528'. Tool open 1 hour, good blow 1 hour. Recovered 2880' salt water. BHP 1400 lbs. IFP 220 lbs. FFP 1305' lbs.
Shale	80	212	
Red Bed & Shells	212	565	
Shale & Shells	565	1445	
Shale & Lime	1445	3065	
Lime	3065	3334	
Lime & Shale	3334	3677	
Lime	3677	4185	
Lime & Shale	4185	4265	
Miss. Chert	4265	4292	
Lime & Shale & Chert	4292	4328	
Lime & Shale	4328	4528	
TOTAL DEPTH 4528'			

STATE OF KANSAS)
) ss:
 COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RECEIVED
 STATE REGISTRATION COMMISSION

JUL 24 1958

REGISTRATION DIVISION
 KANSAS

STRATA DRILLING, INC.

Jim B. McWilliams
 Jim B. McWilliams, Secy-Tres.

Subscribed and sworn to before me this 21th day of July, 1958.

My Commission Expires:
 December 14, 1961

Elaine H. Taylor
 Elaine H. Taylor, Notary Public

PLUGGING
 12 T 29 R 9W
 BOOK PAGE 117 LINE 2