

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

NORTH


Locate well correctly on above  
Section Plat

Kingman County, Sec. 8 Twp. 29S Rge. 9 (E) W (W)  
 Location as "NE/CNW/SW" or footage from lines C NE SW  
 Lease Owner Sierra Petroleum Co., Inc.  
 Lease Name Gaider Well No. 1  
 Office Address 211 N. Broadway, Wichita, Kansas 67202  
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
 Date well completed 10-22 1966  
 Application for plugging filed 10-22 1966  
 Application for plugging approved 10-22 1966  
 Plugging commenced 10-22 1966  
 Plugging completed 10-22 1966  
 Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes Ewing

Name of Conservation Agent who supervised plugging of this well Archie Ewing, Pratt, Kansas  
 Producing formation Depth to top Bottom Total Depth of Well 4591 Feet  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe		-0-	229	8 5/8"	229	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud.  
 #1 plug at 225' w/ 25 sks. cement  
 #2 plug at 40' w/ 10 sks. cement  
 #3 plug in rat hole w/2 sks. cement

RECEIVED  
STATE CORPORATION COMMISSION

OCT 26 1966

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor S & S Drilling Company  
 Address Box 645, Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Barton, ss.

T. D. Sweetman (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) T. D. Sweetman

Box 645, Great Bend, Kansas 67530  
 (Address)

SUBSCRIBED AND SWORN TO before me this 25 day of October, 19 66

My commission expires 5/9/67

Heata L Boyd  
 Notary Public.

SIERRA Petroleum Co. Inc.

WELL LOG  
Gaider # 1  
C NE SW 8-29S-9W  
Kingman County, Kansas

FROM	TO	
0	25	Shale
25	127	Sand
127	229	Shale & Red Bed
229	940	Red Bed
940	1220	Shale
1220	2696	Shale & Lime
2696	2836	Lime
2836	2978	Shale & Lime
2978	3655	Lime & Shale
3655	4105	Lime
4105	4206	Lime & Chert
4206	4231	Chert
4231	4268	Lime
4268	4571	Shale & Lime
4571	4590	Simpson
4590		Total Depth

Elevation: 1700' K.B.

Formation Tops:

Heebner	3389'
Toronto	3404'
Douglas	3422'
Douglas ss	3436'
Brown Lime	3593'
Lansing	3603'
Base KC	4034'
Mississippi	4185'
Kinderhook	4262'
Simpson	4551'
Simpson Sand	4563'
T.D.	4590'

RECEIVED  
S.P. CORPORATION COMMISSION

OCT 31 1966

CONSERVATION DIVISION  
WICHITA, KANSAS

STATE OF KANSAS

COUNTY OF BARTON ss

T. D. Sweetman, Partner of S & S Drilling Company, being first duly sworn on oath says: That I have knowledge of the facts, statements and matters herein contained and the log of the above described well as filed and that the same are true and correct.

*T. D. Sweetman*  
T. D. Sweetman

Suscribed and sworn before me this 25th day of October, 1966.

*Leota S. Boyd*  
Notary Public Barton County

My Commission Expires 5/9/67