

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-095-20,957-0000

LEASE NAME Julius C. Weber #

WELL NUMBER \_\_\_\_\_

SPOT LOCATION SE NW NW

SEC. 8 TWP. 29 SRGE. 9w (E) or (W)

COUNTY Kingman

Date Well Completed \_\_\_\_\_

Plugging Commenced 12/12/85

Plugging Completed 12/17/85

LEASE OPERATOR Keener Oil Company

ADDRESS 320 S. Boston, Suite 406, Tulsa, Ok. 74103

PHONE # (918) 587-4154 OPERATORS LICENSE NO. 7062

Character of Well \_\_\_\_\_  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Wichita

Is ACO-1 filed? \_\_\_\_\_ If not, Is well log attached? \_\_\_\_\_

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 4487'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	215'	none
				4 1/2"	4483 1/2'	2799'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Pumped bottom with 35 sacks cement to 4400'. Shot pipe at 3625', 3520', 3325', and 2799'. Pulled 73 joints of pipe. Plugged well with 3 hulls, 15 gel, & 110 sacks 60/40 poz 2% gel.

Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso

(employee of operator) of

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso Kansas

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 6th day of January, 1985

My Commission expires:



Notary Public

Form CP-4  
Revised 01-84