

TYPE

AFFIDAVIT OF COMPLETION FORM

ACO-1 WELL HISTORY

SIDE ONE DRY HOLE, FILING ONE ORIGINAL, TWO COPIES (3)

ALBERS J #1

Compt. _____

(Rules 82-3-130 and 82-3-107)

DOCKET NO. NP _____

This form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ninety (90) days after the completion of a well, regardless of how the well was completed.

FOR INFORMATION REGARDING THE NUMBER OF COPIES TO BE FILED AND APPLICATIONS REQUIRING COPIES OF ACO-1 FORMS SEE PAGE TWO (2), SIDE TWO (2) OF THIS FORM.

F Letter requesting confidentiality attached.

C Attach ONE COPY of EACH wireline log run (i.e. electrical log, sonic log, gamma ray neutron log etc.)***Check here if NO logs were run _____.

PLEASE FILL IN ALL INFORMATION. IF NOT AVAILABLE, INDICATE. IF INFORMATION LATER BECOMES AVAILABLE, SUBMIT BY LETTER.

LICENSE # 5171 EXPIRATION DATE 6/30/84

OPERATOR TXO Prod. Corp. API NO. 15-095-21,375-0000

ADDRESS 200 W. Douglas, Ste. 300 COUNTY Kingman

Wichita, KS 67202 FIELD Komarek

** CONTACT PERSON Harold R. Trapp PROD. FORMATION dry

PHONE 265-9441 NO Indicate if new pay.

PURCHASER none LEASE Albers

ADDRESS none WELL NO. "J" #1

DRILLING Kandrilco WELL LOCATION App. NW SE SW

CONTRACTOR ADDRESS 555 N. Woodlawn, Bldg. 1, Ste. 207 1940 Ft. from West Line and

Wichita, KS 67208 710 Ft. from South Line of

PLUGGING Sun Oil Well Cementing the SW (Qtr.) SEC 10 TWP 29S RGE 10 (W).

CONTRACTOR ADDRESS P.O. Box 169

Great Bend, KS 67530

TOTAL DEPTH 2650 PBD none

SPUD DATE 9-23-83 DATE COMPLETED 9-27-83

ELEV: GR 1728 DF -- KB 1736

DRILLED WITH (XXX) (ROTARY) (XXX) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE none

Amount of surface pipe set and cemented 8-5/8"@292' DV Tool Used? no

TYPE OF COMPLETION THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil, Shut-in Gas, Gas, Dry, Disposal, Injection, Temporarily Abandoned. If OWWO, indicate type of re-completion. Other completion. NGPA filing.

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

A F F I D A V I T

I, Harold R. Trapp, being of lawful age, hereby certifies that:


I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.

Handwritten signature of Harold R. Trapp

(Name)

SUBSCRIBED AND SWORN TO BEFORE ME this 3rd day of October

19 83.



Handwritten signature of Bonnie J. Holcomb (NOTARY PUBLIC)

MY COMMISSION EXPIRES: 12-23-85

RECEIVED STATE CORPORATION COMMISSION OCT 4 1983

** The person who can be reached by phone regarding any questions concerning this information.

CONSERVATION DIVISION Wichita, Kansas

10-4-83

Side TWO

OPERATOR TXO PROD. CORP.

LEASE NAME Albers

SEC 10 TWP 29S RGE 10 (W)

WELL NO "J" #1

FILL IN WELL INFORMATION AS REQUIRED;

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

Show Geological markers, logs run, or other Descriptive information.

Formation description, contents, etc.	Top	Bottom	Name	Depth
<p>Check if no Drill Stem Tests Run. XX Check if samples sent Geological Survey.</p> <p>Ran O.H. Logs</p> <p>DST #1, 2509-47' (Indian Cave), w/results as follows: IFP/30": 67-40#, weak blow ISIP/60": 873# FFP/30": 67-94#, weak blow FSIP/60": 846# Rec: 180' watery drilling mud, no show of gas</p> <p>If additional space is needed use Page 2</p>			LOG TOPS	
			Herington	1735 +1
			Cottonwood	2270 -534
			Onaga	2511 -775
			Indian Cave "	2518 -782
			Wabaunsee	2558 -822
			RTD	2650
			LTD	2651

Report of all strings set — surface, intermediate, production, etc. CASING RECORD (New) or (NS&A) YYYYY

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8-5/8"	23#	292'	lite	175	
					Class A	100	

LINER RECORD			PERFORATION RECORD		
Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
none	none	none	none	none	none

TUBING RECORD		
Size	Setting depth	Packer set at
none	none	none

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
none	none

Date of first production D&A, 9-27-83	Producing method (flowing, pumping, gas lift, etc.) dry	Gravity none
Estimated Production - I.P. none	Oil none	Gas none
Disposition of gas (vented, used on lease or sold) dry	Water none	Gas-oil ratio none
	Perforations none	

Sun Oilwell Cementing
A Division of BJ Hughes, Inc.

P. O. Box 169
GREAT BEND, KANSAS 67530

CEMENTING TICKET No. **15603**
and Invoice Number

Date	Customer Order No.	Sec.	Twp.	Range	Truck Called Out	On Location	Job Began	Job Completed
9-27-83		19	285	100W	11:00 AM	1:00 PM	2:00 PM	

Owner	Contractor	Charge To
T.Y.O. Production	Kendrick #2	T.Y.O. Production
Mailing Address	City	State

Well No. and Farm	Place	County	State
#1-1 Adhes	Sec 19-285-100W	Kingman	Kansas

Depth of Well	Depth of Job	Casing	Size	Weight	Size of Hole Amt. and Kind of Cement	Cement Left In casing by	Request Necessity
2750	900				1100 Bulk		

Kind of Job	OW	Drillpipe	Rotary	Truck No.
Plug to Abandon	NW	4 1/2"	Cable	#28

Condition of Well at time of Cementing	D+A	Typ of Plugs	D/A
----------------------------------------	-----	--------------	-----

Pressure Circulating	Minimum	Maximum
----------------------	---------	---------

Time Required Mixing Cement	min.	Making Change	min.	Pumping Cement	min.
-----------------------------	------	---------------	------	----------------	------

Remarks: Mixed 100 sk 69/40 bag 370 A-7 - 270 Gal
 1st Plug @ 900 ft w/ 35 sk
 2nd Plug @ 350 ft w/ 35 sk
 3rd Plug @ 60 ft w/ 30 sk
 Rat Hole w/ 10 sk

Price Reference No.	#9
Price of Job	370.00
Second Stage	
Standby Truck	
Other Charges	
Pump Truck Mileage	39.00

Cement: *Deer Run* Material Left on Location: *T. Harker!*

Helper	State	District	State
<i>Steve Brannon</i>	<i>Kansas</i>	<i>McPherson Lodge</i>	<i>Kansas</i>

The above job was done under supervision of the owner, operator, or his agent whose signature appears below.
 State Pluggers on Location: Yes No Agent of Contractor or Operator: *[Signature]*

SALES TICKET FOR MATERIALS

QUANTITY SACKS	BRAND AND TYPE	PRICE	TOTAL
40	Class A	5.00/sk	300.00
40	Deer Run F	2.00/sk	80.00
258	A-7	23.16/sk	59.34
172	GI	6.75/sk	11.61
1-95/8"	Plug Hole		4.00
	Handling and Dumping	.92/sk	73.00
	Delivered by Truck No. 19-47	Mileage 26-4.5mi	79.56
	Delivered From <i>McPherson Lodge</i>	Sales Tax	12.36
	Signature of Operator <i>Arthur Kelly</i>	Total Charges	1052.87

RECEIVED
STATE CORPORATION COMMISSION
OCT 4 1983
CONSERVATION DIVISION
Wichita, Kansas

Date: 9-25-83 Customer Order No. Sec. 10 Twp. 29 Range 10 Truck Called Out On Location 5:00 PM Job Began 7:25 PM Job Completed 7:45 PM
 Owner: TXO PRODUCTION Contractor: KANDRELL #2 Charge To: TXO PRODUCTION
 Mailing Address City State County KANSAS Zip

Depth of Well 297 Depth of Job 291 Place 1/2 E ST. 60 N SIDE Well No. and Farm ALBELS #1 J
 Condition of Well at Time of Cementing NORMAL Pressure Circulating Minimum Maximum

Time Required Mixing Cement Making Change Pumping Cement New Size 8 7/8 Used Weight 73 Size of Hole 12 1/4 Type of Plugs W-R CUP
 Cement Left in casing by Request Necessity 20 feet Drillpipe Rotary Cable #13 Truck No. M. LODGE State KANSAS

Cement: CARRY MOFFAT Kind of Job SURFACE CASING
 Helper: KEVIN BRUBARDT Material Left On Location 8 7/8" PLUG CONT.
 Prices Subject to Correction.

Remarks: RAN 7 JOBS OF 8 7/8 CASING TO 297' CEMENTED WITH 175# LITEWATE, 3% COAL, FOLLOWED WITH 100# CLASS A, 3% COAL, 2% BEI. DISPLAYED TO 271'

Price Reference No.	#1
Price of Job	370.00
Second Stage	
Standby Truck	
Other Charges	
Pump Truck Mileage	45.00

CEMENT DED CALCULATE!

The above job was done under supervision of the owner, operator, or his agent whose signature appears below.

Charles Hammett
Agent of Contractor or Operator

State Plugger on Location Yes No

SALES TICKET FOR MATERIALS

QUANTITY	BRAND AND TYPE	PRICE	TOTAL
100	Common CLASS A	5.00	500.00
175	Litewate	4.20	735.00
	Pozmix-Diamix F		
	Salt-A5		
744#	CcCL-A7	23	17112
188#	AmCL-B1 Gel	16.75	3149
	Plugs 8 7/8" WOODEN RUBBER CUP		40.00
	Delivered by Truck No. T-35 Handling and Dumping 75 Mileage 30		263.16
	Delivered From MEO LODGE Sales Tax 4		21.70
	Signature of Operator (EDWARD)	Total Charges	65457.17