

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 15 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Cities Service Oil Company
Complete Address 3545 NW 58th Street, Oklahoma City, Oklahoma
Lease Name Hoffman "E" Well No. 2
Location G SE NW Sec. 12 Twp. 32 Rge. 34 (E) (W)
County Seward Total Depth 5900'
Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A X
Other well as hereafter indicated None
Plugging Contractor Sage Drillign Co.
Address Wichita, Kansas License No. _____
Operation Completed: Hour 6:10 AM Day 11 Month 5 Year 1973

The above well was plugged as follows:

8 5/8" to 1644' circulated w/ cement. Mud 5900' to 5571'
Spotted 55 sacks cement 5571' to 5421' Mud 5421' to 4220'
Spotted 35 sacks cement 4220' to 4120' Mud 4120' to 2630'
Spotted 70 sacks cement 2630' to 2430' Mud 2430' to 1664'
Spotted 15 sacks cement 1664' to 1619' Mud 1619' to 1060'
Spotted 45 sacks cement 1060' to 925' Mud 925' to 45'
Plug, Hulls & 15 sacks cement 45' to 0'. Halliburton Pump Truck.

I hereby certify that the above well was plugged as herein stated.

Signed: Edward J. Evers
Well Plugging Supervisor

INVOICED
DATE 5/16/73
INV. NO. 9368-11