

DISTRICT CONSERVATION AGENT'S REPORT

*R*

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 23-20

LOCATION NEc SW/4

SEC. 14 TWP. 32S RGE. 34W

Dry Hole \_\_\_\_\_ Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well X

I have today completed supervision of plugging of:

Well No. 1 Lease Stoner

Operator American Gas Production Address Bartlesville, Oklahoma

Field Hugoton County Seward

Total Depth 2775 Feet.

(Describe briefly the manner in which the well was plugged)

Ran Baker C.I. retainer on tubing to 2500 feet.

Squeezed with 200 sacks of cement to 3000#

Cement from 2500 to 2260 feet. Heavy mud from 2260 feet to 500 feet.

Cement from 460 feet to 500 feet. Mud from 460 feet to 50 feet.

Cement from 50 feet to 5 ffet of surface at which point the 8-5/8"

casing was cut off and a steel cap was welded on the 8-5/8" casing.

**PLUGGING**  
FILE SEC 14 T 32 R 34W  
OCT. 23 NOV. 20

RECEIVED  
CORPORATION COMMISSION  
NOV 14 1952  
CONSERVATION DIVISION  
Wichita, Kansas

*R. J. Phillips*  
District Conservation Agent  
Date October 17, 1952