

15-175-20190-0000

R

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

SEP 11 1973

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Patrick Petroleum Corporation

Complete Address 300 Insurance Bldg., Wichita, Kansas 67202

Lease Name Hitch Well No. 1

Location NW NW SE Sec. 31 Twp. 32 Rge. 34 (E) (W)

County Seward Total Depth 6425'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Sargents Casing Pulling

Address Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 5:00PM Day 3 Month 9 Year 1973

The above well was plugged as follows:

8 5/8" to 1708' circulated w/ cement. 5 1/2" to 6240' cemented.

Top perforations 6140' Plug bottom w/ 25 sacks cement.

Top of cement 5950' Mud 5950' to 900'

Spotted 35 sacks cement 900' to 800'. Mud 800' to 45'

Plug, Halls & 15' sacks cement 45' to 0'. Company Pump

Pulled 2404' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

DATE 9-11-73

INV. NO. 7906-W

Signed: Edgar J. Green
Well Plugging Supervisor