

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

SEP 14 1964

Operator's Full Name Walter Kuhn Drilling Co. CONSERVATION DIVISION  
Wichita, Kansas

Complete Address: 726 Union Center, Wichita, Kansas

Lease Name Neuner-Kuhn Well No. # 1

Location C SWE Sec. 29 Twp. 32 Rge. 36 (E)/(W)

County Stevens Total Depth 2755'

Abandoned Oil Well      Gas Well X Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Sargent Casing Pulling Co.

Address: Liberal, Kansas License No. 511

Operation Completed: Hour 9 PM Day 9 Month 9 Year 64

The Above well was plugged as follows:

10 3/4"-640' Circulated w/cement. 5 1/2"-1824'. Packer-6'. 7"-1830' to 2755'

Sand bottom 2755' to 2630' Spotted 20 Sax.cement 2630' to 2542'

Mud 2542' to 650' Spotted 35 Sax.cement 650' to 580'

Mud 580' to 30' Plug, 15 Sax.cement 30" to 0

Company Pump. Pulled 1824' 5 1/2" pipe. Pulled packer. Pulled 910' 7" pipe.

Cut surface off 5' below ground level. Weld plate on surface.

I hereby certify that the above well was plugged as herein stated.

DATE 9/14/64  
INV. NO. 9492-U

Signed: J. P. Roberts  
Well Plugging Supervisor