

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION CSW CSW

SEC. 17 TWP. 32 RGE. 32W

Dry Hole X Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 1 Lease Jones "A"

Operator Prince Brothers Drilling Co. Address Box 992, Electra, Texas

Field \_\_\_\_\_ County Seward

Total Depth 2690 Feet.

Plugging Contractor Arnett Well Plugging Service

Plugging Contractor's License No. 239

Address Hoisington, Kansas

(Describe briefly the manner in which the well was plugged)

Pumped 150 sacks of cement through perforations. Top of cement 2540. Mudded up

550 to 2540. Rock bridge 540 to 550. Dumped 10 sacks of cement 505 to 540 feet.

Baled dry and tested for water. Not water entry. Mudded up 470 to 505

Rock bridge 465 yo 470. Dumped 10 sacks of cement 430 to 465. Left hole open for

farm water well 0 to 430.

**PLUGGING**  
FILE SEC 17 T 32 R 32W  
BOOK PAGE 146 LINE 7

R. J. Philliphaug  
District Conservation Agent  
Date July 28, 1955