

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
APR 1 - 1974  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Texas Energies Inc.

Complete Address 306 Bk of Southwest, Amarillo, Texas 79109

Lease Name Roehr Well No. 1

Location C SW NE Sec. 20 Twp. 32 Rge. 31 (E) (W)

County Seward Total Depth 5903'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated     

Plugging Contractor Knight Casing Pulling

Address Box 405, Chase, Kansas License No. 624

Operation Completed: Hour 7:00PM Day 25 Month 3 Year 1974

The above well was plugged as follows:

8 5/8" to 1384' circulated w/ cement. 5 1/2" to 5901' cemented.

Top perforations 5799' Plug bottom w/ 20 sacks cement.

Top of cement 5500' Mud 5500' to 600'

Spotted 35 sacks cement 600' to 500' Mud 500' to 45'

Plug, Halls & 15 sacks cement 45' to 0'. Halliburton Pump Truck.

Pulled 1750' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 4/2/74

INV. NO. 8855-W