

15-129-00023-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

MAR 5 1964

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Panhandle Eastern Pipe Line Co.

Complete Address: Box 828 Liberal, Kansas

Lease Name Murphy Well No. 1-15

Location C SW Sec. 15 Twp. 32 Rge. (E) (W) 41

County Morton Total Depth 5482'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Sargent Casing Pulling Service

Address: Liberal, Kansas License No. 511

Operation Completed: Hour 4 PM Day 3 Month 3 Year 64

The Above well was plugged as follows:

9 5/8"-1540' Circulated w/cement. 5 1/2"-5482' Cemented.

Bridge plug set at 2152' Top perforations 2115'

Plug bottom w/25 Sax.cement top cement 2000' Mud 2000' to 700'

35 Sax.cement 700' to 610' Mud 610' to 45'

15 Sax.cement 45' to 0

Pulled 1200' 5 1/2" pipe. Company Pump.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 3/5/64

INV. NO. 8444-W