

SP

Form CP-3  
Rev. 6-9-67

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

AUG 23 1967

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Intent to Drill,  
filed August 4, 1967.

Operator's Full Name Colorado Oil Company

Complete Address 915 Union National Bldg., Wichita, Kansas 67202

Lease Name Prouse Well No. # 1

Location NE SW SW Sec. 31 Twp. 30 Rge. 6 (E) (W) W

County Kingman Total Depth 4410'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated     

Plugging Contractor Gabbert-Jones, Inc.

Address 830 Sutton Place, Wichita, Ks. 67202 License No.     

Operation Completed: Hour 11:00 A.M. Day 21st Month August Year 1967

The above well was plugged as follows:

250' of 8 5/8" surface pipe, cement circulated with 180 sacks. Hole was  
filled with drilling mud to 240', 1st cementing plug, bridged with 2 sacks  
of dry cement and 1/2 sack of hulls on fluid at 240', and cemented with 23  
sacks, with cement from 230' to 155'. Hole was filled with drilling mud  
to 40', 2nd cementing plug, bridged with 1 sack of dry cement and 1/2 sack  
of hulls on fluid at 40', and cemented with 9 sacks, with cement from 30'  
to the base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving  
Well Plugging Supervisor

DATE 8-23-67

INV. NO. 6192-W