

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

OCT 3 1966

CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Colorado Oil Company

Complete Address: 915 Union National Bldg., Wichita, Kansas

Lease Name Allender Well No. # 1

Location C SW NW Sec. 30 Twp. 30 Rge. 6 (E) (W) W

County Kingman Total Depth 4725'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 11:15AM Day 28th Month Sept. Year 1966

The Above well was plugged as follows:

213' of 8 5/8" surface pipe, cement circulated. 4383' of 4 1/2" long string,
cemented with 175 sacks. Plug back T.D. 4272'. Top perferation 4267'.
Bottom of the hole was sanded to 4250', and cemented with 3 sacks, through
the dump bailer. 3382' of 4 1/2" long string was recovered from the hole.
Hole was filled with mud to 210', rock bridge from 210' to 200', and
cemented with 25 sacks. Hole was filled with mud to 40', rock bridge from
40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 10/3/66
INV. NO. 4035-W

Signed: Audrie Elving
Well Plugging Supervisor