

7  
KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

OCT 24 1966

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Sierra Petroleum Company, Inc.

Complete Address: 211 North Broadway, Wichita, Kansas

Lease Name Gaider Well No. # 1

Location C NE SW Sec. 8 Twp. 29 Rge. 9 (E) (W) W

County Kingman Total Depth 4591'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: S & S Drilling Company

Address: Box 645, Great Bend, Kansas License No. \_\_\_\_\_

Operation Completed: Hour 6:00AM Day 22nd Month Oct. Year 1966

The Above well was plugged as follows:

229' of 8 5/8" surface pipe, cement circulated with 225 sacks. Hole  
was filled with drilling mud to 225', 1st cementing plug, bridged with  
2 sacks of dry cement and 1/2 sack of hulls on fluid at 225', and cemented  
with 23 sacks. Hole was filled with drilling mud to 40', 2nd cementing  
plug, bridged with 1 sack of dry cement and 1/2 sack of hulls on fluid  
at 40', and cemented with 9 sacks to the base of the cellar. Rat hole  
bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 10/24/66

INV. NO. 4165-U