

Form CP-3  
Rev. 6-26-62KANSAS  
STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

MAR 8 1967

CONSERVATION DIVISION  
Wichita, KansasJ. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, KansasIntent to Drill,  
filed March 1, 1967.Operator's Full Name Sierra Petroleum Company, Inc.Complete Address: 211 North Broadway, Wichita, KansasLease Name McKenna Well No. # 1Location C SW SW Sec. 3 Twp. 29 Rge. 9 (E) (W) WCounty Kingman Total Depth 3010'Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A XOther well as hereafter indicated:                     Plugging Contractor: S & S Drilling CompanyAddress: Box 645, Great Bend, Kansas License No.             Operation Completed: Hour 4:00AM Day 6th Month March Year             

The Above well was plugged as follows:

238' of 8 5/8" surface pipe, cement circulated with 200 sacks. Fluid  
level in the hole was at 114', 1st cementing plug and 1 sack of hulls  
was pushed in fluid to 220', and cemented with 25 sacks, through the  
drill pipe at 220'. Hole was filled with drilling mud to 35', 2nd  
cementing plug, bridged with 1 sack of hulls on fluid at 35', and  
cemented with 8 sacks to the base of the cellar. Rat hole bridged  
and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE

3/8/67

INV. NO.

4880-WSigned: Archie Elving  
Well Plugging Supervisor