

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 58-8LOCATION CNWSEC. 16 TWP. 33S RGE. 43WDry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Addington "B"Operator Cities Service Oil Company Address Box 70, Liberal, KansasField _____ County MortonTotal Depth 5140 Feet.Plugging Contractor _____ Daco Lease & Well Servicing Co.,Plugging Contractor's License No. 138Address _____ Borger, Texas

(Describe Briefly the manner in which the well was plugged)

Mixed 100 sacks cement, pumped plug to 2550'; squeezed to 800#; reclaimed 1061'of 5½" casing; filled hole with heavy rotary mud to 20' of ground level; cementto 4' of surface at which point the surface was cut off and a steel cap welded onthe 8-5/8" casing.

R. J. Phillips
District Conservation Agent

Date July 10, 1956

FILED
CONSERVATION

8-21-56 AUG 21 1956

CONSERVATION DIVISION
Wichita, Kansas

