

KANSAS

Form CP-3
Rev. 6-4-68

R

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15-095-20536-0000 RECEIVED
STATE CORPORATION COMMISSION
(this well)

DEC 23 1976

Operator's Full Name Maurice L. Brown Co
Complete Address 1500 Vickers KSB&T Bldg Wichita, KS
Lease Name Lindholm B Well No. 1
Location NW/NE/NW Sec. 22 Twp. 28 Rge. 5 (E) (W) W
County Kingman Total Depth 3940
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Voth Casing Pulling Co
Address 715 S. Ave Arkansas City, KS License No. 684
Operation Completed: Hour 4:00 PM Day 21 Month 12 Year 1976

CONSERVATION DIVISION
Wichita, Kansas

The above well was plugged as follows:

261 ft 8 5/8 surface cemented with 250 sacks. 3940 ft 5 1/2 long string
cemented with 150 sacks. Top perf. 3804 ft. Sand to 3780 ft, 5
sacks cement with bailer. Pulled 3070 ft 5 1/2. Set 10 ft rock bridge
at 250 ft. Fill hole with 4 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Russell B. Buler
Well Plugging Supervisor

DATE 12-23-76
INV. NO. 4375-W