

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

NOV 16 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Petroleum Inc.

Complete Address: 352 North Broadway, Wichita, Kansas

Lease Name Griffith Unit Well No. # 1

Location Appr. C S/2 SE SE Sec. 29 Twp. 29 Rge. 8 (E) (W)

County Kingman Total Depth 4350

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Garvey Drilling Company

Address: Route 2, Great Bend, Kansas License No.

Operation Completed: Hour 1:00PM Day 13th Month Nov. Year 1964

The Above well was plugged as follows:

221' of 8 5/8" surface pipe, cement circulated with 200 sacks. Hole
was filled with drilling mud to 225', 1st cementing plug, bridged
solid with dry cement and hulls, and cemented with 25 sacks. Hole
was filled with drilling mud to 40', 2nd cementing plug, bridged solid
with hulls and dry cement, and cemented with 10 sacks to the base of
the cellar. Rat and mouse hole bridged and cemented with 4 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 11/16/64

INV. NO. 191-W