

4
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

FEB 21 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Well Plugging Authority,
issued February 9, 1967.

Operator's Full Name Mobil Oil Corporation

Complete Address: Box 1828, Oklahoma City, Oklahoma

Lease Name J. F. Birkenbaugh Well No. # 1

Location W/2 SW Sec. 15 Twp. 29 Rge. 7 (E) (W) W

County Kingman Total Depth 4521'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Forbes Casing Pulling, Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 11:30AM Day 17th Month Feb. Year 1967

The Above well was plugged as follows:

253' of 8 5/8" surface pipe, cemented with 300 sacks. 4513' of 5 1/2" long
string, cemented with 200 sacks. Top perferation 3728'. Plug was pushed
to 3700', 30' of sand, and cemented with 5 sacks, through the dump bailer.
3300' of 5 1/2" long string was recovered from the hole. Hole was filled with
mud to 250', rock bridge from 250' to 240', and cemented with 25 sacks.
Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented
with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 2/21/67

INV. NO. 4998-W

Signed: Archie Elving
Well Plugging Supervisor