

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

FEB 10 1967

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Well Plugging Authority,  
issued January 13, 1967.

Operator's Full Name Spector Pipe & Supply, Inc.

Complete Address: Box 169, Russell, Kansas

Lease Name Bates Well No. # 1

Location SW SW NE Sec. 15 Twp. 29 Rge. 7 (E) (W) W

County Kingman Total Depth 4503'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Lynch Casing Pulling Company

Address: R. R. # 4, Great Bend, Kansas License No. 457

Operation Completed: Hour 4:30PM Day 6th Month Feb. Year 1967

The Above well was plugged as follows:

325' of 8 5/8" surface pipe, cement circulated . 4499' of 5 1/2" long  
string, cemented with 200 sacks. No record of any perferations. Plug  
and 50' of sand to 3438', and cemented with 5 sacks, through the dump  
bailer. 3325' of 5 1/2" long string was recovered from the hole. Hole was  
filled with mud to 300', rock bridge from 300' to 280', and hole was  
filled with 4 yards of ready-mix cement from 280' to the base of the  
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 2/10/67  
INV. NO. 4740-U