

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 14 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Mack Oil Company

Complete Address: 812 Union Center, Wichita, Kansas

Lease Name Castle Well No. # 1

Location C SW SW Sec. 17 Twp. 29 Rge. 7 (E) (W) W

County Kingman Total Depth 4585

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Great Bend, Kansas License No. 436

Operation Completed: Hour 10:30AM Day 13th Month July Year 1964

The Above well was plugged as follows:

279' of 8 5/8" surface pipe, cement circulated. 4508 of 4 1/2" long string,
cemented with 190 sacks. Plug back to 4361'. Top perforation 4133'. Bot-
tom of the hole was sanded to 4100', and cemented with 3 sacks. Hole was
filled with mud to 250', bridged with 10' of rock, at 250', and cemented
with 25 sacks. Hole was filled with mud to 40', bridged with 10' of rock,
at 40', and cemented with 10 sackss to base of the cellar.
3450' of 4 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

DATE 7/14/64
INV. NO. 9490-W

Signed: Archie Elving
Well Plugging Supervisor