

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION

APR 24 1972

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name McCoy Petroleum Co.

Complete Address 502 Union Center Wichita, Ks

Lease Name Castle Well No. 1

Location G NE/SE Sec. 17 Twp. 29 Rge. 7 (E) (W) W

County Kingman Total Depth 4250

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Santa Fe Pipe & Supply Co. Inc.

Address Box 562 Great Bend, Ks License No. 574

Operation Completed: Hour 1:00 PM Day 20 Month 4 Year 1972

The above well was plugged as follows:

220 ft 8 5/8 surface pipe cement circulated. 4249 ft 5 1/2 long string  
cemented with 175 sacks. Top perf. 4144 ft. Sand back to 4120 ft,  
5 sacks cement with bailer. Pulled 3138 ft 5 1/2/ Set 10 ft rock bridge  
at 190 ft. Fill hole with 3 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED

DATE 4/27/72

INV. NO. 5610-W