

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JUN 7 1974

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Robert F. White

Complete Address 1014 Union Center Wichita, KS

Lease Name Brand Well No. 1-0WVO

Location NE/NW/NE Sec. 17 Twp. 29 Rge. 7 (E) (W)

County Kingman Total Depth 4245

Abandoned Oil Well        Gas Well X Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Russ Casing Pulling Co Inc

Address Box 1082 Great Bend, KS License No. 623

Operation Completed: Hour 3:00 PM Day 5 Month 6 Year 1974

The above well was plugged as follows:

251 ft 8 5/8 surface cement circulated. 4245 ft 4 1/2 long string  
cemented with 150 sacks. Top perf. 4155 ft. Sand to 4100 ft, 4  
sacks cement with bailer. Pulled 1640 ft 4 1/2. Set 10 ft rock bridge  
at 360 ft. Fill hole with 7 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed [Signature]  
Well Plugging Supervisor

DATE 6/11/74  
INV. NO. 9275-W