

¹⁰
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC - 7 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Lee Phillips Oil Company

Complete Address: 1532 Wichita Plaza, Wichita, Kansas

Lease Name Brand Well No. # 1

Location NE NW NE Sec. 17 Twp. 29 Rge. 7 (E) (W) W

County Kingman Total Depth 4550'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Rex & Morris Drilling Company

Address: Box 334, El Dorado, Kansas License No. _____

Operation Completed: Hour 10:00PM Day 1st Month Dec. Year 1965

The Above well was plugged as follows:

246' of 8 5/8" surface pipe, cement circulated with 200 sacks. Hole
was filled with drilling mud to 240', 1st cementing plug, bridged solid
with dry cement and hulls on fluid at 240', and cemented with 25 sacks.
Hole was filled with drilling mud to 40', 2nd cementing plug, bridged
solid with dry cement and hulls on fluid at 40', and cemented with 10
sacks to the base of the cellar. Rat hole bridged and cemented with
2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 12-8-65
INV. NO. 2364-W

Signed: Archie Elving
Well Plugging Supervisor