

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

JAN 2 1968

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Original Well Plugging Authority,  
issued April 11, 1967. Renewal  
Authority, issued December 5, 1967.

Operator's Full Name Robert F. White

Complete Address: 714 Union Center Bldg., Wichita, Kansas 67202

Lease Name Endicott Well No. # 1

Location C N/2 NE NE Sec. 22 Twp. 29 Rge. 7 (E) (W) W

County Kingman Total Depth 4497'

Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated:       

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas 67524 License No. 436

Operation Completed: Hour 3:30PM Day 30th Month December Year 1967

The Above well was plugged as follows:

375' of 8 5/8" surface pipe, cement circulated. 4486' of 5 1/2" long string, cemented with 100 sacks. This is an open hole. Bottom of the hole was sanded to 4450', and cemented with 5 sacks, through the dump bailer, with cement from 4450' to 4410'. 3890' of 5 1/2" long string was recovered from the hole. Fluid level in the hole was at 300', bridge plug and rock bridge from 300' to 290', and cemented with 25 sacks, with cement from 290' to 215'. Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented with 10 sacks, with cement from 30' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving  
Well Plugging Supervisor

INVOICED

DATE 1-2-68

INV. NO. 7018-W