



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
9-14-64  
SEP 14 1964

Dear Sir:

Mr. Kuhn of Walter Kuhn Drilling Co. has this

date requested permission to plug the following described well:

Mr. Kuhn guarantees payment of the plugging fee.

Operator's full Name: Walter Kuhn Drilling Co.

Complete Address: 726 Union Center, Wichita, Kansas

Lease Name: Neuner-Kuhn Well No. # 1

Location: C 8W SE Sec. 29 Twp. 32 Rge. 36 (E)(W)

County Stevens Total Depth 2755' Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Kuhn was instructed to plug the well as follows:

- 10 3/4" 640' Circulated w/cement. 5 1/2"-1824' Packer-6' 7"-1830'-2755'
- Sand 2755' to 2630' Spotted 20 Sax.cement 2630' to 2542'
- Mud 2542' to 650' Spotted 35 Sax.cement 650' to 580'
- Mud 580' to 30' Plug 15 Sax.cement 30' to 0'

Very truly yours,

*[Signature]*  
Conservation Division Agent