



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
APR 1 - 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Geoffroy of Texas Energies has this

date requested permission to plug the following described well:

Mr. Geoffroy guarantees payment of the plugging fee.

Operator's full Name: Texas Energies Inc.

Complete Address: 306 Bank Of Southwest, Amarillo, Texas

Lease Name: Roehr Well No. 1

Location: C SW NE Sec. 20 Twp. 32 Rge. 31 XX (E) (W)

County: Seward Total Depth 5903' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Geoffroy was instructed to plug the well as follows:

8 5/8" to 1384' circulated w/ cement. 5 1/2" to 5901' cemented.


Top perforations 5799' Plug bottom w/ 20 sacks cement.

Top of cement 5500' Mud 5500' to 600'

Spot 35 sacks cement 600' to 500' Mud 500' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,


Conservation Division Agent