



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

RECEIVED
 STATE CORPORATION COMMISSION

MAR 5 1964

CONSERVATION DIVISION
 Wichita, Kansas

Dear Sir:

Mr. Sutton of Panhandle Eastern Pipe Line Co. this date requested permission to plug the following described well:

Mr. Sutton guarantees payment of the plugging fee.

Operator's full Name: Panhandle Eastern Pipe Line Co.

Complete Address: Box 828 Liberal, Kansas

Lease Name: Murphy Well No. 1-15

Location: C SW Sec. 15 Twp. 32 Rge. (E) (W) 41

County Morton Total Depth 5482' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Sutton was instructed to plug the well as follows:

9 5/8"-1540' Circulated w/cement. 5 1/2"-5482' Cemented.

Bridge plug set at 2151' Top perforations 2115'

Plug bottom w/25 Sax.cement top cement 2000'. Mud 2000' to 700'

35 Sax.cement 700' to 610' Mud 610' to 45'

15 Sax.cement 45' to 0

Very truly yours,

[Signature]
 Conservation Division Agent