

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

AUG 23 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Intent to Drill,
filed August 4, 1967.

Dear Sir:

Mr. T. F. Brown of Gabbert-Jones, Inc. has this

date requested permission to plug the following described well:

Mr. Brown guarantees payment of the plugging fee.

Operator's full Name: Colorado Oil Company

Complete Address: 915 Union National Bldg., Wichita, Kansas 67202

Lease Name: Prouse Well No. # 1

Location: NE SW SW Sec. 31 Twp. 30 Rge. 6 (E)(W) W

County Kingman Total Depth 4410' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Brown was instructed to plug the well as follows:

250' of 8 5/8" surface pipe, cement circulated with 180 sacks. Fill
hole with drilling mud to 240', 1st cementing plug, bridge with 1/2 sack
of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Audie Elving
Conservation Division Agent