

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JAN 4 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Kuhn of Graves Drlg. Co has this
date requested permission to plug the following described well:

Mr. Kuhn guarantees payment of the plugging fee.

Operator's full Name: National Oil Co.

Complete Address: 200 W Douglas Wichita, KS

Lease Name: Drouhard Well No. 1

Location: SW/NE/NE Sec. 25 Twp. 30S Rge. 6 (E)(W) W

County: Kingman Total Depth 4585 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Kuhn was instructed to plug the well as follows:
293 ft 8 5/8 surface pipe cemented with 250 sacks. Fill
hole to 290 ft, plug, 1/2 sack hulls, 25 sacks cement. Mud
to 40 ft, plug, 1/2 sack hulls, 10 sacks cement to surface.
2 sacks cement in rat hole.

Very truly yours,

[Signature]
Conservation Division Agent