

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 24 1967  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Intent to Drill,  
filed October 6, 1967.

Dear Sir:

Mr. Rod Sweetman of S & S Drilling Company has this  
date requested permission to plug the following described well:

Mr. Sweetman guarantees payment of the plugging fee.

Operator's full Name: Beacon Resources Corporation

Complete Address: 412 Union Center Bldg., Wichita, Kansas 67202

Lease Name: Shore Well No. # 1

Location: NW SE NW Sec. 25 Twp. 30 Rge. 6 (E)(W) W

County Kingman Total Depth 4590' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Sweetman was instructed to plug the well as follows:

280' of 8 5/8" surface pipe, cement circulated with 250 sacks. Fill  
hole with drilling mud to 260', bridge with 1/2 sack of hulls the 1st  
cementing plug, and cement with 25 sacks. Fill hole with drilling mud  
to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement  
with 10 sacks to base of cellar. Bridge and cement rat hole with 2 sacks

Very truly yours,

Archie Elving  
Conservation Division Agent