

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Intent to Drill,  
filed February 5, 1968.

Dear Sir:

Mr. Garry Richards of Pickrell Drilling Company has this  
date requested permission to plug the following described well:

Mr. Richards guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drilling Company

Complete Address: 705 Fourth National Bank Bldg., Wichita, Ks. 67202

Lease Name: Cotton "A" Well No. # 1

Location: C N/2 NE NE Sec. 24 Twp. 30 Rge. 6 (E)(W) W

County Kingman Total Depth 4126' Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Richards was instructed to plug the well as follows:

214' of 8 5/8" surface pipe, cement circulated with 150 sacks. Fill  
hole with drilling mud to 200', 1st cementing plug, bridge with 1/2 sack  
of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',  
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10  
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

RECEIVED Very truly yours,  
STATE CORPORATION COMMISSION

FEB 14 1968  
Archie Elving  
Conservation Division Agent  
Wichita, Kansas