



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

6-4-82

VERBAL PERMIT FORM
(To be filed by Plugging Agent)
15-129-20632-0000

Dear Sir:

Mr. Daniel Cox of City Service Co. has this date requested permission to plug the following described well:

Operator's Full Name: City Service Co.

Complete Address: 3545 N. W. 28th St. Oklahoma City Okla 73112

Lease Name: Collingwood Well No. C4

Location: 810 FNL-660 FEL Sec. 13 Twp. 33 Rge. 43 (E) (W)

County: Morton Total Depth: 4750'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Cox was instructed to plug the well as follows:

They cement circulated 13.54' of 8 5/8" surface casing. 1st plug at 4600' with 50 sbs of cement. 2nd plug at 3620' with 35 sbs of cement. 3rd plug at 1400' with 50 sbs of cement. 4th plug at 680' with 25 sbs of cement. 5th plug at 40' to 0' on solid bridge with 10 sbs of cement. Then they circulated 10 sbs of cement in rat hole. The cement was pumped through drill pipe. The plugging was accomplished by Dowell Cementing Co.

Very truly yours,

RECEIVED
STATE CORPORATION COMMISSION

JUN - 8 1982

CONSERVATION DIVISION
Wichita, Kansas

Paul A. Luttie
Conservation Division Agent

INVOICE and WELL PLUGGING AUTHORITY

June 14, 1982

INVOICE NUMBER: 412-W

TO: Cities Service Company
3545 N.W. 58th St.
Oklahoma City, OK, 73112

PAYABLE UPON RECEIPT

PLUGGING ASSESSMENT AS FOLLOWS:

Collingwood "C"-4

810' FNL & 660' FEL, Sec. 13-33S-43W

Morton

T.D. 4750'

\$154.38

Wakefield Drilling Co., Inc.

NOTE: We also need the following before our file is completed:

- x _____ Well Plugging Record (CP-4)
- x _____ Well Log
- x _____ Well Plugging Application (CP-1)

WELL PLUGGING AUTHORITY

Gentlemen:

This is your authority to plug the above subject well in accordance with the rules and regulations of the state corporation commission.

This authority is void after ninety (90) days from the above date.



 Administrator

 Mr. Paul Luthi Box 495 Minneola Ks. 67112 (316) 885-4838

is hereby assigned to supervise the plugging of the above mentioned well.