

RECEIVED 5-14
KANSAS CORPORATION COMMISSION

2-070456 167
R

MAY 27 1992

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202
CONSERVATION DIVISION
WICHITA, KS

15-095-00704-0000

API NUMBER: 12/7/50

SW SW NE, SECTION 21 TOWNSHIP 28 RANGE 5W

OPERATOR LICENSE # 5003 2970 FEET FROM S SECTION LINE
2310 FEET FROM E SECTION LINE

OPERATOR McCoy Petroleum Corp.
NAME & 110 S. Main, #500
ADDRESS Wichita, KS 67202

LEASE NAME: Bolinger A #1
COUNTY: Kingman
WELL TOTAL DEPTH: 3836' 124.67

CONDUCTOR PIPE:

SURFACE CASING: 8-5/8" @ 207'

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED:

PLUGGING CONTRACTOR:
ADDRESS: LICENSE:

COMPANY TO PLUG AT: HOUR: 10:00 DAY: 14 MONTH: 5 YR: 1992

PLUGGING PROPOSAL RECEIVED FROM: Darrell Hanson
COMPANY NAME: McCoy Petroleum PHONE:

WERE: CIBP @ 3750' & 2 sx common - 30 sx @ 700' - 300' to surface.

PLUGGING PROPOSAL RECEIVED BY: Steve Van Gieson

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (X) PART () NONE ()

COMPLETED: HOUR: 4:00 DAY: 14 MONTH: 5 YEAR: 1992

ACTUAL PLUGGING REPORT:
Set CIBP @ 3750' & ran 2 sx common on top - shot 5-1/2" csg off @ 700' - pumped 35 sx there - pulled to 300' & circ cmt to surface.

REMARKS: Halliburton 60/40 4%

I DID OBSERVE THIS PLUGGING.

INVOICED

DATE 6-3-92

INV. NO. 35367

/s/ Jack Luthi (AGENT)

DW