

2 040308

2-20-87

13/R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 095-20,625-0000

SE NE SW, SEC. 26, T 29 S, R 7 W/XX

1650 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5038

Lease Name Reed Well # A-1

Operator: Robinson Oil Company

County Kingman 138.91

Name & Address 737 RH Garvey Building

Well Total Depth 4274 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 258

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, KS 67524

Company to plug at: Hour: _____ Day: _____ Month: _____ Year: 19 _____

Plugging proposal received from _____

(company name) Kelso Casing Pulling (phone) _____

were: Sand to 4100 and four sacks, 3 hull, 15 gel, 110 sacks, 60/40 poz, 4% gel.

PBTD - 4235'

4 1/2" - 4270'

Perf. - 4130'-4142'

4206'-4216

Plugging Proposal Received by Warren Kirkpatrick (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 12:30 Day: 20 Month: 2 Year: 19 87

ACTUAL PLUGGING REPORT Kelso Casing Pullers dumped sand inside the 4 1/2" casing to

4100' and capped with four sacks of cement to cover the perforations. The 4 1/2" was shot off and recovered from 3600'. The well was plugged by pumping three sacks of hulls,

15 sacks of gel and 50 sacks of cement, a wiper plug and 60 sacks of cement.

RECEIVED STATE CORPORATION COMMISSION

MAR 25 1987

Remarks: Allied #2552 MX 600# SI 500# CONSERVATION DIVISION Wichita, Kansas

(If additional description is necessary, use BACK of this form.)

INVOICED (If additional description is necessary, use BACK of this form.)

DATE 3-26-87

Signed [Signature] (TECHNICIAN)

INV. NO. 16437

2-20