

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
130 S. Market, Room 2078  
Wichita, Kansas 67202

API NUMBER: 15-095-21739-0000

12-16-97

SECTION 28 TOWNSHIP 29 RANGE 07W

OPERATOR LICENSE # 31532 330 FEET FROM S SECTION LINE

OPERATOR Bison Production Co. 1960 FEET FROM E SECTION LINE

NAME & 9320 E. Central

ADDRESS Wichita, KS 67206

LEASE NAME: Weve #1-28

COUNTY: KM

WELL TOTAL DEPTH: 4199' 136, 47

PIPE: \_\_\_\_\_

SURFACE CASING: 8 5/8" @ 215'

ABANDONED OIL WELL \_\_\_\_\_ GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SWD \_\_\_\_\_ D&A

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

**RECEIVED**  
KANSAS CORPORATION COMMISSION

PLUGGING CONTRACTOR: Duke Drilling co, Inc.

JUN 01 1998

ADDRESS: P.O. Box 823, Great Bend, KS 67530 LICENSE: 5929

COMPANY TO PLUG AT: HOUR: 10:00 DAY: 16 MONTH: 12 YR: 1997

CONSERVATION DIVISION  
WICHITA, KS

PLUGGING PROPOSAL RECEIVED FROM: Steven Anderson

COMPANY NAME: Bison Engineering PHONE: (316) 636-1801

WERE: 1150' - 35 sacks; 750' - 35 sacks; 265' - 35 sacks; 60' - 25 sacks; 25 sacks - rat hole.


PLUGGING PROPOSAL RECEIVED BY: SVG

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL ( ) PART ( ) NONE (  )

COMPLETED: HOUR: 3:00 DAY: 16 MONTH: 12 YEAR: 1997

ACTUAL PLUGGING REPORT: Pulled drill pipe to 1150'. Pumped 35 sacks. Pulled to 750' pumped 35 sacks. Pulled to 265'. Pumped 35 sacks. Pulled to 60'. Pumped 25 sacks. Ran joint of drill pipe in rat hole. Pumped 25 sacks.

REMARKS: Allied 60/40 POZ, 4% Gel.

I DID NOT OBSERVE THIS PLUGGING.  
  
JACK LUTHI

FORM CP-2/3  
REV. 3/90

**INVOICED**

DATE 6-2-98

INV. NO. 50647