

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-00728-00-00  
Spot: NESESW Sec/Twnshp/Rge: 28-29S-7W  
990 feet from S Section Line, 2970 feet from E Section Line  
Lease/Unit Name: ROHLMAN Well Number: 1  
County: KINGMAN Total Vertical Depth: 4290 feet

Operator License No.: 31191  
Op Name: R & B OIL & GAS, INC.  
Address: 904 N. LOGAN PO BOX 195  
ATTICA, KS 67009

Production Casing Size: 5.5 feet: 4288  
Surface Casing Size: 5.625 feet: 250

*\$ 13943*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/17/2003 8:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: \_\_\_\_\_

Proposed  
Plugging  
Method:

AS REQUIRED

RECEIVED  
KCC DISTRICT #2  
OCT 2 2003  
WICHITA, KS

Plugging Proposal Received By: STEVE VANGIESON  
Date/Time Plugging Completed: 04/21/2003 10:00 AM

Witness Type: Plugging Operations Partially Witnessed  
KCC Agent: STEVE VANGIESON

**Actual Plugging Report:**

THE PERFS WERE COVERED WITH SAND TO 4130' AND CAPPED WITH 5 SKS OF CEMENT. THE CASING WAS RECOVERED FROM 2631', AND PULLED TO 1200', WHERE 35 SKS OF CEMENT WAS SPOTTED. THE CASING WAS PULLED TO 700', WHERE 35 SKS OF CEMENT WAS SPOTTED. THE CASING WAS PULLED TO 300', WHERE CEMENT WAS CIRCULATED TO SURFACE.

RECEIVED  
KANSAS CORPORATION COMMISSION  
OCT 06 2003  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: ALLIED CEMENTING 60/40 4% GEL

Plugged through: CSG

District: 02

Signed \_\_\_\_\_

INVOICED (TECHNICIAN)

DATE 10.6.03  
NO. 2004060583