

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-00995-00-00  
Spot: CSWSESW Sec/Twnshp/Rge: 29-29S-7W  
330 feet from S Section Line, 1650 feet from W Section Line  
Lease/Unit Name: ELMER OAK Well Number: 2  
County: KINGMAN Total Vertical Depth: 4519 feet

Operator License No.: 6236  
Op Name: M.T.M. PETROLEUM  
Address: PO BOX 82  
SPIVEY, KS 67142

Conductor Pipe: Size \_\_\_\_\_ feet: 3146.87  
Surface Casing: Size 8.625 feet: 293 215 SX CMT  
Production: Size 5.5 feet: 4250 125 SX CMT  
Liner: Size \_\_\_\_\_ feet: \_\_\_\_\_

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/09/2002 6:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: JOE MAES Company: QUALITY WELL SERVICE, INC Phone: (316) 727-3410

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: Plugging Operations Partially Witnessed  
Date/Time Plugging Completed: 07/09/2002 6:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

The perfs were covered w/sand to 4130' and capped w/5sxs of cement. Contractor miss read perfs and didn't get sand high enough. Mud fell in on sand when casing was shot loose. The 5 1/2" was recovered from 3100' and pulled to 1150', where 35sxs of cement was spotted. The casing was pulled to 700' where 35sxs of cement was spotted. The casing was pulled to 340' where cement was circulated to surface.

RECEIVED  
KCC DISTRICT #2

JUL 15 2002

WICHITA, KS

Remarks: UNITED CEMENT 60/40 POZ, 4% GEL

Plugged through: CSG

District: 02

Signed \_\_\_\_\_

(TECHNICIAN)

INVOICED

DATE 7-22-02

INV. NO. 2003060077