

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-21814-00-00
Spot: S2SW Sec/Twnshp/Rge: 29-29S-7W
660 feet from S Section Line, 1320 feet from W Section Line
Lease/Unit Name: ELMER OAK Well Number: A#1
County: KINGMAN Total Vertical Depth: 4505 feet

Operator License No.: 6236
Op Name: M.T.M. PETROLEUM
Address: PO BOX 82
SPIVEY, KS 67142

Conductor Pipe: Size feet: 8 1/4 6-41
Surface Casing: Size 8.625 feet: 220
Production: Size feet:
Liner: Size feet:

Well Type: DH UIC Docket No: Date/Time to Plug: 07/25/2002 12:00 PM
Plug Co. License No.: 5123 Plug Co. Name: PICKRELL DRILLING COMPANY, INC.
Proposal Rcvd. from: MIKE KERNS Company: PICKRELL DRILLING CO., INC. Phone:

Proposed Plugging Method: 35sxs-1300', 35sxs-700', 35sxs-270', 25sxs-60'. 15sxs in rathole.

Plugging Proposal Received By: STEVE VANGIESON
Date/Time Plugging Completed: 07/25/2002 12:00 PM

WitnessType: Plugging Operations Were Not Witnessed
KCC Agent: STEVE VANGIESON

Actual Plugging Report:

The drilling pipe was run open end to 1300' where 35sxs of cement was spotted. Pull drill pipe to 700', spotted 35sxs of cement. Pull drill pipe to 270' spotted 35sxs cement. Pulled drill pipe to 60' circulated 25sxs cement to surface. Circulated 15sxs in rathole.

RECEIVED
KCC DISTRICT #2

AUG 02 2002


WICHITA, KS

Remarks: ALLIED CEMENT # 09835 60/40, 4% GEL.

Plugged through: DP

District: 02

Signed



(TECHNICIAN)

INVOICE

DATE

8-5-02

INV. NO.

2003060164