

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-20057-00-01
Spot: CSENW Sec/Twnshp/Rge: 36-29S-8W
3300 feet from S Section Line, 3300 feet from E Section Line
Lease/Unit Name: ALBRIGHT Well Number: 1
County: KINGMAN Total Vertical Depth: 4235 feet

Operator License No.: 31142 Conductor Pipe: Size feet: 9137.64
Op Name: PETROLEUM PROPERTY SERVICES, INC. Surface Casing: Size 8.625 feet: 233 185 SX CMT
Address: 155 N. MARKET, STE 1010 Production: Size 4.5 feet: 4265 125 SX CMT
WICHITA, KS 67202 Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 07/29/2002 11:30 AM

Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone:

Proposed Plugging Method: Perfs 4182'-92'. Sand to 4130' and 4sxs. 35sxs @ 1250', 35sxs @ 850'. Circulate cement from 280'.

Plugging Proposal Received By: STEVE VANGIESON

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 07/29/2002 11:30 AM

KCC Agent: STEVE VANGIESON

Actual Plugging Report:

The perf were covered w/sand from 4235'-4119' and capped w/4sxs of cement. The casing was recovered from 3422' and pulled to 1250' spotted 35sxs cement. Pulled to 850' spotted 35sxs cement. Pulled to 280' and circulated cement to surface. Pulled remaining casing and topped off cement.

RECEIVED
KCC DISTRICT #2

AUG 02 2002

WICHITA, KS

Remarks: UNITED CEMENT 60/40, 4% GEL

Plugged through: CSG

District: 02

Signed

(TECHNICIAN)

INVOICED

DATE 8-5-02

FILE NO. 2003060163