

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
130 S. Market, Room 2078  
Wichita, Kansas 67202

5-12

15-095-00537-0000

API NUMBER: Drilled 1952

SW-SW-SE SECTION 35 TOWNSHIP 29 RANGE 8W

OPERATOR LICENSE # 6236  
OPERATOR MTM Petroleum  
NAME 100 S. Main P O Box 7  
ADDRESS Spivey KS. 67142

330 FEET FROM S SECTION LINE  
2310 FEET FROM E SECTION LINE  
LEASE NAME: Cline #1  
COUNTY Kingman  
WELL TOTAL DEPTH: 4290  
PIPE: 5 1/2 @ 4289  
SURFACE CASING 10 3/4 @ 235

139.43

RECEIVED  
KANSAS CORPORATION COMMISSION

ABANDONED OIL WELL \_\_\_\_\_ GAS WELL X INPUT WELL \_\_\_\_\_ SWD \_\_\_\_\_ D&A \_\_\_\_\_ MAY 19 1999

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_  
CONSERVATION DIVISION  
WICHITA, KS

PLUGGING CONTRACTOR: Quality Well Service  
ADDRESS: Sterling KS. LICENSE: 31925

COMPANY TO PLUG AT: HOUR: \_\_\_\_\_ DAY: \_\_\_\_\_ MONTH: \_\_\_\_\_ YR: \_\_\_\_\_

PLUGGING PROPOSAL RECEIVED FROM: Richard McIntyre

COMPANY NAME: Quality Well Service PHONE: \_\_\_\_\_

WERE: Perfs 4148-4182

Sand to 4040 and 5 sacks of cement.  
Shoot pipe off, pull to 1150 spot 35 sacks of cement. Pull pipe to 750 spot 35  
sacks of cement. Pull pipe to 285 and circulate cement to surface.

PLUGGING PROPOSAL RECEIVED BY: Steve VanGieson

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL ( ) PART ( ) NONE ( X )

COMPLETED: HOUR: 1730 DAY: 12 MONTH: 5 YEAR: 1999

ACTUAL PLUGGING REPORT: Sand was dumped inside the pipe to cover the perforations at  
4040' and capped with 5 sacks of cement. The pipe was recovered from 3002' and  
pulled to 1150, where 35 sacks of cement was spotted. The pipe was pulled to 750'  
where 35 sacks of cement was spotted. The pipe was pulled to 285' where cement  
was circulated to surface. The remaining pipe was pulled and the hole was topped  
off with cement.

REMARKS: Allied Cementing 60/40 Poz 4 % gel

I DID OBSERVE THIS PLUGGING.  
[Signature]  
Steve VanGieson

FORM CP-2/3  
REV. 3/90

INVOICED

DATE 5-21-99

INV. NO. 60964

5-12

AUG 03 1999