

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-00162-00-03
Spot: NENENE Sec/Twnshp/Rge: 35-29S-8W
330 feet from N Section Line, 330 feet from E Section Line
Lease/Unit Name: SCHWARTZ Well Number: 1
County: KINGMAN Total Vertical Depth: 4337 feet

Operator License No.: 31191
Op Name: R & B OIL & GAS, INC.
Address: 904 N. LOGAN PO BOX 195
ATTICA, KS 67009

Conductor Pipe: Size feet: 3 1/40.95
Surface Casing: Size 8.625 feet: 217
Production: Size 4.5 feet: 4336 175 SX CMT
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 01/16/2002 11:00 AM
Plug Co. License No.: 30346 Plug Co. Name: SHAWNEE WELL SERVICE, INC.
Proposal Rcvd. from: JEFF CAPPS Company: SHAWNEE WELL SERVICE, INC. Phone: (620) 254-7251

Proposed
Plugging
Method:

Perfs 4162'-4172'. CIBP 4100' and 1sxs cement. 35sxs-1200'. 35sxs-800'. Circulated from 260'-0'.

Plugging Proposal Received By: STEVE VANGIESON
Date/Time Plugging Completed: 01/16/2002 11:00 AM

WitnessType: Plugging Operations Were Not Witnessed
KCC Agent: STEVE VANGIESON

Actual Plugging Report:

A CIBP was set at 4100' to cover the perfs. The CIBP was capped w/1sx of cement. The casing was recovered from 2900' and pulled to 1201', where 35sxs of cement was spotted. Thru casing was pulled to 814' where 35sxs of cement was spotted. The casing was pulled to 258', where cement was circulated to surface.

RECEIVED
KCC DISTRICT #2

FEB 27 2002


WICHITA, KS

Remarks: ALLIED CEMENTING 60/40 4% GEL.

Plugged through: CSG

District: 02

Signed



(TECHNICIAN)

INVOICED

DATE 3-04-02

INV. NO. 2002061436