

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-00536-00-00 Spot: CSESESW
Sec: 34 Twnshp & Dir: 29 S Rng & Dir: 8 W
Feet: 330 frm N/S: S Feet: 2970 frm E/W: E
Lease/Unit Name: McCOY Well Number: 1
County: KINGMAN Total Vertical Depth: 4241 feet

Operator License No.: 31142
Operator Name: Petroleum Property Services, Inc
Address: 155 N. Market. STE 1010
Wichita, KS 67202

6/13

Conductor Pipe: Size feet:
Surface Casing: Size 8.62 feet: 202
Production: Size 4.5 feet: 4240 137.83

Well Type: GAS UIC Docket No: Date/Time to Plug: 06/13/2000 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: Quality Well Service, Inc.
Proposal Received from: Geo Mace Company Name: Quality Well Serv.
OpRepPhoneNo: (316) 278-2476

Were: Sand to 4080' and 4sxs. 35sxs-1250. 35sxs-800. 250-0'

Plugging Proposal Received By: Jack Luthi WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 06/13/2000 12:00 AM

Actual Plugging Report:

Sanded bottom to 4080' and 4sxs of common shot 4 1/2" casing off @2615'. Pulled to 1250' pumped 35sxs. Pulled to 800'. Pumped 35sxs pulled to 250' cir cement to surface. Before we pumped cement @ 1250' we pumped 10sxs of gel and 200lbs of hulls. Well circulated

RECEIVED
KCC DISTRICT #2
JUN 14 2000
WICHITA, KS

Remarks: United #2826 60/40 4%gel
Anhydrite Plug: No BottomPlug: No DakotaPlug: No
Plugged through:

I (did / did not) observe this plugging

INVOICED
DATE: 6/15/00
WV. No. 61869
Signed Jack Luthi
(TECHNICIAN)

(Signature)